

PLINTH AREA RATES**as on 01.04.2025**

Rate in ₹ per sqm

S. No.	Description	Non-Residential Buildings			Residential Buildings	
		Offices/ Colleges	Hospitals	Schools	Hostels	Quarters
1.0	BUILDING COST (Specifications as per Annexure-I)					
1.1	RCC FRAMED STRUCTURE (Upto six storeys)					
1.1.1	Floor height 3.60 metre	30,920	31,990	23,530	-	
1.1.2	Floor height 3.00 metre	-	-	-	24,410	
1.2	COMPOSITE (PARTIALLY LOAD BEARING AND PARTIALLY RCC FRAMED) STRUCTURE (Upto six storeys)					
1.2.1	Floor height 3.60 metre	26,280	27,190	20,000		
1.2.2	Floor height 3.00 metre	-	-		20,750	
1.3	EXTRA FOR					
1.3.1	Set of six additional storey (i.e. from 7 th to 12 th storey)	123				
	Similarly, extra for next set of six storeys may be increased by Rs. 123/- per sqm (viz Rs. 246/- per sqm for 13 th to 18 th storey, Rs. 369/- per sqm for 19 th to 24 th storey, Rs 492/- per sqm for 25 th to 30 th storey and so on). The applicable plinth area shall be the sum of plinth area of all the storeys within the set of six storeys. If the next set of storeys is having fewer than six storeys, the same procedure shall be followed. For example, if building is having 15 storeys, the additional rate applicable shall be (i) Rs 123/- per sqm for sum of plinth area between 7 th to 12 th storey and (ii) Rs. 246/- per sqm for sum of plinth area of 13 th to 15 th floor.					
1.3.2	Every 0.3 metre or part thereof, additional / less height of floor above normal floor height of 3.60 metre / 3.00 metre (on areas having additional / less height)	434				
1.3.3	Every 0.3 metre or part thereof, higher plinth height over normal plinth height of 0.60 metre (on ground floor area only).	470				
1.3.4	Every 0.30 metre or part thereof, deeper foundations over normal depth of 1.20 metre (on ground floor area only).	205				
1.3.5	Making stronger foundations to take load of one additional floor at a later date (on ground floor area only).	For RCC framed structures			Composite structure	
		1800			700	
1.3.6	RCC raft foundation (on ground floor area only)	12,765				
1.3.7	Pile foundation upto a depth of 15 metre (on ground floor area only)	22,240				

Plinth Area Rates 2025

S. No.	Description	Non-Residential Buildings			Residential Buildings	
		Offices/ Colleges	Hospitals	Schools	Hostels	Quarters
1.3.8	Every 1.0 m deeper pile foundation over normal depth of 15 metre (on ground floor area only)	2,265				
1.3.9	Stronger structural members to take heavy load above 500 kg per sqm upto 1000 kg per sqm.	2,070				
1.4	BASEMENT FLOOR					
1.4.1	Floor height upto 3.35 metre including water proofing (excluding raft base)	23,170				
1.4.2	Add or deduct for every 0.30 metre, or part thereof, height against normal height of 3.35 metre.	1,140				
1.5	FIRE FIGHTING					
1.5.1	Downcomer System	460				
1.5.2	With wet riser system	890				
1.5.3	With wet riser and sprinkler system	1,200				
1.6	FIRE ALARM SYSTEM					
1.6.1	Manual fire alarm system	280				
1.6.2	Automatic fire alarm system	600				
1.7	Pressurized mechanical ventilation system in the basements with supply duct of exhaust blowers (on areas where mechanical ventilation is required)	1,050				
1.7	Pressurized mechanical ventilation system in the basements with supply duct of exhaust blowers (on areas where mechanical ventilation is required)	1,050				
1.8	STILT PORTION					
1.8.1	Stilt portion of multi-storey buildings upto floor height of 3.60 metre (on stilt area only)	9,870				
1.8.2	Every 0.30 metre additional height above 3.60 metre	235				
2.0	SERVICES(Percentage below refers to the percentage of building cost as per 1.0 above excluding sub head 1.3.4, 1.3.5, 1.3.6, 1.3.7, 1.3.8, 1.3.9,1.5 & 1.6)					
2.1	Internal water supply & sanitary installations	4%	10%	5%	12% with attached toilets, 8% with common toilets.	9%

S. No.	Description	Non-Residential Buildings			Residential Buildings	
		Offices/ Colleges	Hospitals	Schools	Hostels	Quarters
2.2	External service connections and local body approval charges shall be as hereunder or as per estimates given by the local body whichever is higher					
2.2.1	Electrical external service connections	3.75%	3.75%	3.75%	3.75%	3.75%
2.2.2	Civil external service connections	1.25%	1.25%	1.25%	1.25%	1.25%
2.2.3	Local body approvals including tree cutting etc.	1.25%	1.25%	1.25%	1.25%	1.25%
2.3	Internal electric installations	12.5%	12.5%	12.5%	12.5%	12.5%
2.4	EXTRA FOR					
2.4.1	Power wiring and plugs	4%	4%	4%	4%	4%
2.4.2	Lightning conductors	0.25%	0.25%	0.25%	0.25%	-
2.4.3	Telephone conduits	0.25%	0.25%	0.25%	0.25%	-
3.0	TPQA & CONSULTANCY SERVICES (Percentage below refers to the percentage of building cost (Sum of Sno. 1.0 & 2.0 above))					
3.1	Third Party Quality Assurance	1%	1%	1%	1%	1%
3.2	Consultancy Services for Architectural, Structural and MEP Services, if outsourced	1.75%	1.75%	1.75%	1.75%	1.75%

S.No.	Capacity/ Persons	Speed in m/sec	Travel height	Price (in lac ₹)	Extra for each additional floor (in ₹)
1	2	3	4	5	6
4.0	LIFTS with power operated centre opening doors and AC variable voltage & variable frequency controls				
4.1	Passenger lifts				
4.1.1	8	1.0	G+4	17.24	99,860
4.1.2	8	1.5	G+5	19.39	99,860
4.1.3	13	1.0	G+4	19.39	99,860
4.1.4	13	1.5	G+5	21.55	1,22,050
4.1.5	16	1.0	G+4	25.85	1,22,050
4.1.6	16	1.5	G+5	28.01	1,22,050
4.1.7	16	2.5	G+12	75.41	1,22,050
4.2	Bed Lifts				
4.2.1	20	0.75	G+4	25.85	1,22,050
4.2.2	20	1.5	G+5	29.09	1,22,050

Plinth Area Rates 2025

S.No.	Capacity/ Persons	Speed in m/sec	Travel height	Price (in lac ₹)	Extra for each additional floor (in ₹)
4.2.3	20	2.5	G+12	80.79	1,22,050
4.3	Goods lifts (2 speed)				
4.3.1	1 Ton	0.5	G+4	28.01	94,310
4.3.2	2 Ton	0.5	G+4	35.55	94,310
4.3.3	3 Ton	0.25	G+4	44.17	1,10,950

S. No.	Description	Rates in ₹
5.0	RCC WATER TANK	
5.1	Overhead tank without independent staging	23 per litre
5.2	Overhead tank with staging height upto 20 metre	35 per litre
5.3	Overhead tank with staging height above 20 metre upto 30 metre	40 per litre
5.4	Overhead tank with staging height above 30 metre upto 40 metre	47 per litre
5.5	Underground sump	24 per litre
6.0	DEVELOPMENT OF SITE	
6.1	Levelling	160 per sqm
6.2	Internal roads & paths	
6.2.1	Internal road with WBM and bituminous top	1,940 per sqm
6.2.2	Internal road with WMM and bituminous top	2,150 per sqm
6.2.3	Cement concrete pavement with vacuum dewatered concrete	2,945 per sqm
6.2.4	Footpath with PCC base, 60 mm thick paver blocks and kerb stone edging	2,930 per sqm
6.3	External sewerage	4,180 per metre
6.4	Filtered water supply	
6.4.1	Distribution lines upto 100 mm dia	2,170 per metre
6.4.2	Peripheral grid 150 mm to 300 mm dia pipes	4,175 per metre
6.4.3	Unfiltered water supply distribution lines	1,560 per metre
6.5	Storm water drains	10,810 per metre
6.6	Rain water harvesting (RWH) (excluding collection tank)	2,330 per metre
6.7	Trenches for services	7,460 per metre
6.8	Boundary wall with 1500 mm high wall and 600 mm high MS grill including 2100 mm high steel gates at every 100 metres	
6.8.1	With brickwork structure with RCC column of size 300X300mm @ 3.00 metre centre to centre and RCC plinth beam of size 300X300mm at ground level and coping	13,210 per metre
6.8.2	Precast RCC wall in M40 grade concrete comprising shaped 250 x 230 mm RCC posts fixed in ground and 70 mm thick RCC wall panel inserts.	9,735 per metre
6.9	Horticulture Works	

S. No.	Description	Rates in ₹
6.9.1	Horticulture operations including 300mm earth filling, grassing, tree plantations/shrubs and potted plants etc.	578 per sqm
6.9.2	Vertical plantations (Excluding the cost of frame work for vertical gardening) (Note: Rate are applicable on vertical gardening area)	6,683 per sqm
7.0	SPECIALISED E&M WORKS	
7.1	33 kV RECEIVING SUBSTAION AND 33 kV/11 kV HT CABLING	
7.1.1	Supplying, installation, testing and commissioning of 33 kV substation comprising 33 kV HT panel, transformers 33kV/11 kV, 11 kV HT panel, inter connections, 11 kV HT underground cabling to the distribution substations on ring main system, substation earthing, substation safety equipment.	3,800 per kVA
7.2	SUB-STATION EQUIPMENT	
7.2.1	Supplying, installation, testing and commissioning of 33 KV/0.433 KV substation equipment comprising HT panel, transformers, HT cable, bus trunking from transformer to LT panel, LT panels, automatic power factor correction panel, active harmonic filters, TVSS (transient voltage suppression system), SPD (surge protection system), essential panel, earthing, required inter-connections, substation safety equipments including LT cabling from substation to the buildings fed by the substation.	9,000 per kVA
7.2.2	Supplying, installation, testing and commissioning of 11 KV/0.433 KV substation equipment comprising HT panel, transformers, HT cable, bus trunking from transformer to LT panel, LT panels, automatic power factor correction panel, active harmonic filters, TVSS (transient voltage suppression system), SPD (surge protection system), essential panel, earthing, required inter-connections, substation safety equipment including LT cabling from substation to the buildings fed by the substation.	8,100 per kVA
	Note: For assessment of kVA estimation of a building, para 4.4, 13 and other relevant paras of "Guidelines for Substation & Power Distribution Systems of Buildings-2019" which is available on CPWD website may be referred to.	
7.3	DIESEL GENERATING SETS	
7.3.1	Supplying, installation, testing and commissioning of silent type DG sets, AMF panel, bus ducting/ cables from DG sets to essential panel, synchronizing panel where required, DG set enclosure room sound insulation/ventilation/smoke exhaust as required, earthing of DG set system, control cabling, fuel tank/piping, DG set exhaust piping/ exhaust chimney as per CPCB norms, civil works connected with DG sets including foundation as required.	11,560 per kVA
7.3.2	Extra for synchronizing panels wherever required	1,070 per kVA
7.4	UNINTERRUPTED POWER SUPPLY	
7.4.1	Supplying, installation, testing and commissioning of online 3 phase UPS system with 30 minutes back up including batteries, interconnecting cables, battery racks etc.	21,290 per kVA
7.4.2	Add for every additional 30 minutes backup	9,580 per kVA
7.5	CENTRAL AC PLANT	
7.5.1	Supplying, installation, testing and commissioning of energy efficient central AC plant including low side works	90,380 per TR

Plinth Area Rates 2025

S. No.	Description	Rates in ₹
7.5.2	Extra for stand-by chilling units high side	40,860 per TR
7.6	VRV/ VRF AC System	
7.6.1	Supplying, installation, testing and commissioning of VRV/VRF system including indoor /outdoor units, piping, electrical power distribution/wiring, electrical panel, treated fresh air system etc.	58,480 per HP
7.7	PRECISION AIRCONDITIONING SYSTEM	
7.7.1	Supplying, installation, testing and commissioning of precision air conditioning system including piping, electrical cabling, controller etc. required for the system	1,10,000 per TR
7.8	SOLAR PHOTO VOLTAIC POWER GENERATION SYSTEM	
7.8.1	Supplying, installation, testing and commissioning of grid interactive roof top solar photo voltaic power generation system including space frame	58,480 per kWp
7.9	SOLAR WATER HEATING SYSTEM	
7.9.1	Supplying, installation, testing and commissioning of solar water heating system with heat exchanger type including electrical heater backup, make up water tank but without piping.	23,920 per 100 litre
7.10	CCTV SYSTEM	
7.10.1	Supplying, installation, testing and commissioning of IP based CCTV system for building security comprising of PTZ / fixed camera, cabling, recording, display system and hard ware software support – for indoors only {Rate applicable on total plinth area}.	210 per sqm
7.10.2	For external surveillance (Rate applicable on total plot area minus plinth area at ground floor)	210 per sqm
	Note: Rate includes peripheral IP based PTZ camera besides indoor camera at reception, corridors, lift lobby etc., wiring upto CCTV room and setting up monitoring unit/units, as required. It will not cover in sides office room/labs, special video walls etc.	
7.11	ACCESS CONTROL SYSTEM	
7.11.1	Supplying, installation, testing and commissioning of access control system for building security comprising of controller, E&M locks, reader, smart cards, cabling, recording, display system, hardware and software support as required (Rate applicable only on plinth area of high security area in the building)	220 per sqm
7.12	IBMS: INTEGRATED BUILDING MANAGEMENT SYSTEM	
7.12.1	Supplying, installation, testing and commissioning of integrated building management system for digital/electronic display and monitoring of all E&M systems like substation, DG sets, UPS, solar power, lifts, AC plants, ventilation systems, fire protection systems, pumps etc. to include cabling, monitors, recording, display system, hardware, software support (upto 10,000 sqm) (Rate applicable on total plinth area)	430 per sqm
7.12.2	Add extra for built up area above 10,000 sqm (Rate applicable on total plinth area)	130 per sqm
7.13	HYDROPNEUMATIC WATER SUPPLY SYSTEM	
7.13.1	Supplying, installation, testing and commissioning of hydro pneumatic water supply system consisting of pumps, pneumatic tank, microprocessor based control panel, VFD, inter connecting pipes, valves, cabling, switchgear etc. as required	1,640 per LPM

S. No.	Description	Rates in ₹
7.14	LIGHTING AUTOMATION INCLUDING OCCUPANCY SENSORS	
7.14.1	Supplying, installation, testing and commissioning of lighting automation including occupancy sensors (Rate applicable on area to be specified by client)	220 per sqm
7.15	BASIC HOME SECURITY FOR RESIDENTIAL COLONY	
7.15.1	Supplying, installation, testing and commissioning of basic security system in the residential colony to include control room at the gate and intercom connection to each dwelling unit, and basic IP based CCTV system to be installed at the entry and exit points, parking areas, entry point of each dwelling unit and other common areas as required including CCTV control room, required under ground cabling, digital recording system and monitor/monitors in the control room:	
7.15.2	Intercom system (Rate applicable on plinth area excluding service/common areas).	320 per sqm
7.16.3	CCTV system (Rate applicable on plinth area excluding service/common areas).	320 per sqm
7.17	LAN SYSTEM	
7.17.1	Supplying, installation, testing and commissioning of LAN system comprising of core switches & L2 switches with 10 G, 10 giga SFP modules, WIFI access points, WIFI controller, network management software, racks, CAT 6A cable, patch panels, OFC etc. (Rate applicable on plinth area excluding service/common areas).	560 per sqm
7.18	IP BASED EPABX SYSTEM	
7.18.1	Supplying, installation, testing and commissioning of IP based EPABX system comprising of core switches & L2 switches with 10 G, 10 giga SFP modules, industry standard appliance server, cloud-based, enterprise-grade UC solution, MID/ENTRY level IP/SIP phone with, dual 1 gig ports, racks, CAT 6A cable, patch panels, OFC etc. (Rate applicable on plinth area excluding service/common areas).	580 per sqm
	NOTE: It will be economical to use common infrastructure of switches, OFC, CAT 6A cable for both voice and networking.	
7.19	Conference hall: supplying, installation, testing and commissioning of audio visual/conference system (Rate applicable on carpet area of Hall only)	11,890 per sqm
7.19	STREET LIGHTING WITH LED	
7.19.1	Supplying, installation, testing and commissioning of LED street/compound/ high mast/ pathway/ landscape lighting for the entire campus (Rate applicable on total plot area).	160 per sqm
	Note: This is applicable for plot sizes more than 1 acre. For smaller plot sizes actual requirements may be worked out	
	Note:- Cost for general façade lighting, if required, with IP 66/67 LED fixtures (RGB/Tunable/Mono) along with controls (hardware and software) and cabling may be assessed on case to case basis.	

Plinth Area Rates 2025

S. No.	Description	Rates in ₹
7.20	STP/ETP PLANT	
	Supplying, installation, testing and commissioning of STP/ETP of appropriate technology including civil works (except plant room), tertiary treatment etc. for the building/ campus	
7.20.1	Plant size upto 50KLD	75,000 per KLD
7.20.2	Add extra for every KLD for plant size above 50 KLD and upto 100 KLD	60,000 per KLD
7.20.3	Add extra for every KLD for plant size above 100 KLD	50,000 per KLD
7.21	DRIVER FACE AND AUTOMATIC NUMBER PLATE RECORDING SYSTEM/RECOGNITION SYSTEM	
7.21.1	Supplying, installation, testing and commissioning of driver face and automatic number plate recording system/ recognition system including high resolution camera and software set for the driver face capture and automatic number plate recording.	7,70,890 per set
7.22	BAGGAGE SCANNERS	
7.22.1	Baggage scanner small: computer based multi energy X-Ray baggage inspection system mounted on castor wheels capable of passing through bags of dimensions 540 mm (W) x 350 mm (H), belt height 750 mm to 850 mm, 22"/24" LCD Monitor, Input / Output rollers with frames etc. as required.	22,59,510 per unit
7.22.2	Baggage scanner big: computer based multi energy X-Ray baggage inspection system capable of passing through bags/parcels of dimension 940mm (W) x 640mm (H) with Belt Height– 750mm–850mm with 22"/24" LCD Monitor, Input/ Output rollers with frames etc. as required.	37,21,550 per unit
7.23	DOOR FRAME METAL DETECTOR	
7.23.1	20 zone or above door frame metal detector nominal size: 760 mm (W) x 2050 mm (H) x 700 mm (D) loaded with necessary software	3,72,160 per set
7.24	MODULAR OPERATION THEATER	
7.24.1	MOT comprising of walls & ceiling system for operating area, steel framework, static dissipative flooring, laminar flow, double dome OT light, touch screen surgeon's control panel, scrub station, X-Ray viewing screen, hatch box, automatic sliding doors, anesthesia pendent, surgeon pendent etc.	
7.24.2	With stainless steel technology	72,00,000 per OT
7.24.3	With SMS technology	105,00,000 per OT
	Note: The above rates are based on OT size of 50 sqm	
7.25	BOOM BARRIER	
7.25.1	Electromechanical boom barrier with all accessories upto 6 metre length.	1,25,000 each
7.26	CAR PARKING SYSTEM	
7.26.1	Sensor based car parking system with controller, display etc. as required. (cost based on minimum car capacity of 250)	10,000 per car
7.27	EMERGENCY LIGHT & ILLUMINATED SIGNAGES	
7.27.1	Illuminated signages (Rate applicable on total plinth area)	22 per sqm
7.28	Motorized steel gates upto 6.00 metre width	5,00,000 per gate

Notes:

1. The rates are inclusive of CP & OH, GST and Labour Welfare Cess (any other Cess/Levy imposed by local Government shall be added separately).
2. The Third Party Quality Assurance (**Item 3.1**) and Consultancy Services for designing and planning of the project (**Item 3.2**), shall only be considered if so desired by the clients.
3. Cost for providing accessibility features for barrier free built environment-
 - i) For New Construction: Cost is deemed included in the rate for non-residential buildings.
 - ii) For Existing Construction: The estimate may be prepared, as per requirement, on the basis of prevalent Delhi Schedule of Rates.
4. If it is not feasible to compute the area or length of development components from item no. 6.1 to 6.7, the cost of these components may be worked out as below on the basis of percentage of building cost as per serial number 1.0.

4.1	Compact site, comprising of a single huge area building with a few ancillary buildings around or few blocks of high rise (higher than 12 storeys) building blocks in close cluster.	4.5% of building cost
4.2	Semi compact/semi scattered site comprising of few blocks of midrise (between 6 to 12 storeys) buildings in a gated compound.	6.0% of building cost
4.3	Large site comprising of various scattered low rise (upto 4 storey) buildings with exception of a block or two upto 6 storeys.	7.5% of building cost

5. Cost of the following development works are not included in these rates.
 - a. Tube wells, pumps, open wells, treatment plant, extension of lines from source of local bodies, head works at water source etc.
 - b. Sewage pumps, sewage treatment plants, septic tanks, extension of outfall sewer upto point of disposal etc.
6. Provision for Specialized E&M services if required may be made as per 6.0 above.
7. Concealed wiring shall be used in all electrical works
8. The rates for the following green measures are already included for civil & electrical works -
 - a. Over deck insulation and application of high SRI reflective paint on thereof.
 - b. Masonry work in super structure with autoclave aerated concrete (AAC) blocks/ fly ash bricks.
 - c. Window with reflective glass coating / high performance coatings / double glazed unit.
 - d. Paints with low VOC options.
 - e. Provision of pillar cock having infrared sensor and foam flow technology along with provisions of online water filter for sediment free water from terrace tank outlet or the distribution line.
 - f. Dual plumbing system.
 - g. LED light fixtures.
 - h. BEE certified 5 star rated fixtures.

ANNEXURE –VI

PROFORMA FOR CALCULATION OF BUILDING COST INDEX

PART C - FORM 1 FOR CALCULATION OF BUILDING COST INDEX									
S. No	Description	Unit	%age	Rates as on 01.04.2025 (in ₹)	Proportionate value (in ₹)	Weightage rates (in ₹)	Weightage of Component	Rates at the time of revision of Cost Index	Cost Index
1	Bricks (Fly Ash)	1000 nos.	100%	4750.00	4750	4750.00	8.00	-	-
2	Cement (OPC)	qtl.	100%	523.45	523.45	523.45	14.50	-	-
3	TMT Steel Reinforcement bar								
a.	8 & 10 mm dia.	qtl.	50%	5430.00	2715.00	5530..	19.50	-	-
b.	12 & 16 mm dia.		50%	5630.00	2815.00			-	-
4	Aggregates 20 mm a) Natural sources	cum	75%	1500.00	1125.00	1375.00	6.50	-	-
	b) Aggregates 20 mm (RCA)		25%	1000.00	250.00			-	-
5 (a)	Sand (coarse sand) Natural sources	cum	75%	1250.00	937.50	1260.00	3.00	-	-
(b)	Sand (coarse sand) RA		25%	1290.00	322.50			-	-
6	Flooring Items								
a.	Vitrified tiles	sqm	50%	380.00	190.00	658.07	5.00	-	-
b.	Ceramic tiles		20%	352.00	70.40			-	-
c.	Kota stone		10%	376.74	37.67			-	-
d.	Granite stone		20%	1800.00	360.00			-	-
7	Paints								
a.	Synthetic enamel paint	litre	33.33%	178.00	59.33	167.67	3.00	-	-
b.	Acrylic washable distemper		33.33%	38.00	12.67			-	-
c.	Premium acrylic paint		33.33%	287.00	95.66			-	-
8	Door/windows-wooden/ uPVC/aluminum/steel								
a.	35 mm thick flush door shutters both side commercial veneering	sqm	30.00%	2120.00	636.00	2601.00	7.00	-	-
b.	Factory made, standard Z-section steel windows		15.00%	1750.00	262.50			-	-
c.	uPVC windows		20.00%	4400.00	880.00			-	-
d.	Aluminum window		35.00%	2350.00	822.50			-	-
9	Pipes								
a.	15 mm GI pipes	metre	10.00%	110.00	11.00	350.00	2.50	-	-
b.	100 mm CI pipes		40.00%	710.00	284.00			-	-
c.	20 mm black conduits		20.00%	80.00	16.00			-	-
d.	20 mm CPVC pipes		30.00%	130.00	39.00			-	-

Plinth Area Rates 2025

S. No	Description	Unit	%age	Rates as on 01.04.2023 (in ₹)	Proportionate value (in ₹)	Weightage rates (in ₹)	Weightage of Component	Rates at the time of revision of Cost Index	Cost Index
10	Lamps & Fans								
a.	Ceiling fans 1200 mm	each	50%	1315.00	657.50	816.40	4.50		
b.	1200 mm LED tube lights with fittings		40%	383.00	153.20				
c.	LED bulbs9/11 W		10%	57.00	5.70				
11	Electrical machinery, Motor 7.5 HP (pump set) 1500 RPM	each	100%	29500.00	29500.00	29500.00	2.50		
12	Wires & cables								
a.	Copper wire 1.5 sqmm	100 metre	70%	1280.00	896.00	1861.40	4.00		
b.	Copper wire 4.0 sqmm		30%	3218.00	965.40				
13	Labour								
a.	Skilled	each	50%	981.00	490.50	893.00	20.00		
b.	Unskilled		50%	805.00	402.50				
Total							100.00		

Note:-

- In the above proforma at S. No. 4 & S. No. 5, Aggregates – 20 mm and Sand (coarse sand) are considered in two parts (a) & (b) respectively where (a) represents 75% from natural source and (b) represents 25% RCA/RA. In areas where components of RCA/RA are not available (because of non-setting up of C&D waste conversion units), the components of aggregate 20 mm at 25% RCA and coarse sand at 25% RA can be avoided and 100% of these materials from natural sources only be considered.
- In the above proforma the rates for building materials adopted in column 5 and corresponding computed rates in column 6 & column 7 are bare rates excluding GST or any other levy. Therefore, for working out local cost index prevailing bare rates only at the respective station shall be considered.